ARMORKORE
BUILT TO ENDURE.
HDPE CLIMATE PROOF/OUTDOOR CABINETRY

Cabinet Specifications

General- All Cabinets

- Finish Height = 34.5”.
- Fabricated entirely with 3/4” HDPE Materials.
- Minimum 2” turndown at top, level to doors/drawers.
- Nailers at top to enable attaching sub base and/or counter.
- 4” Toe Kicks Including Spacers.
- Factory Installed Back Panels.
- Applied End Panels on each side of Islands-No Toe Kick.
- Sleepers installed on all floors, shelves and upper cabinets (Smokers) as Needed.
- Standard Pulls, Hinges and Slides (Identified).
- Any deviation from these details will be considered custom.

Standard Cabinets

- Height = 34.5 Inches (Not Including Counter Tops)
- Depth = 28 Inches (Finished Including Doors and Back Panel)

BBQ Cabinets

- Height = 34.5 Inches (Not Including Counter Tops)
- Depth = 32 Inches (Finished Including Doors and Back)
- Add 6 Inches to Cabinet Cut-Out Dimensions-Sides & Below.
- 4 Door Lower Cabinets open to Upper to Accommodate Utilities.

Equipment Cut-Outs (I.E. BBQs,Side Burners, Sink/Prep Stations, ETC.)

- All Equipment Must Have Manufacturer Recommended Cutout Details.
- BBQs/Side Burners/Etc. Face Exposed Counter Mount Cabinets.
  - Width Add 1”
  - Depth Add 1/2”
  - *Height Delete 1/2” (Approximately 1” Gap Below EQ. Varied by Counter Top Thickness)
  - Counter Tops Will Overhang Cabinets to Accommodate Actual Cutout Details.
  - Door Style Cabinets Open to Accommodate Utilities.
- Sinks/Cooler/Etc. 100% Counter Mounted Equipment Cabinets.
  - Check Cut-Out Detail To Insure Proper Size Cabinet.
  - 10” Turndown Level with Doors.
  - Door Style Cabinets Open to Accommodate Utilities.
  - Installed by Counter Top Fabricator.

***Height Cut-Out Set Based on Most Common Counter Top Thickness (1-3/8”). Gap Below BBQ Will Vary as Counter Top Thickness Varies.**

X_____

Customer Acknowledgement

X_____

Customer Acknowledgement